STATE OF NEW HAMPSHIRE INTER-DEPARTMENT COMMUNICATION

DATE:

October 3, 2018

FROM:

Matt Urban

Chief, Operations Mgmt. Section

AT (OFFICE):

Department of Transportation

SUBJECT

Dredge & Fill Application

Derry-Londonderry, 13065

Bureau of Environment

TO

Gino Infascelli, Public Works Permitting Officer

New Hampshire Wetlands Bureau 29 Hazen Drive, P.O. Box 95 Concord, NH 03302-0095

Forwarded herewith is the application package prepared by Fuss & O'Neill, Inc. for NH DOT for the subject Major impact project. This project is classified as Major per Env-Wt 303.02(c). The Towns of Derry and Londonderry, New Hampshire, and the New Hampshire Department of Transportation (NHDOT), in cooperation with the Federal Highway Administration (FHWA) are proposing the construction of a new interchange with I-93 (known as Exit 4A) and other transportation improvements to reduce congestion and improve safety along State Route 102 (NH 102).

Due to the fact that this is a "Design Build" project this application package includes conceptual plans that encompass the anticipated greatest extent of impacts for the project (an impact envelope approach). As the "Design Build" project moves forward into final design the Department will submit an application update accounting for the anticipated impact reductions in comparison to the overall total permitted impacts.

Using the anticipated greatest extent of impacts the Department has estimated that mitigation could be in the magnitude of approximately \$2.8 Million when estimating for wetland impacts, river impacts, secondary impacts, and vernal pool impacts. As this "Design Build" project progresses into final design impacts will be reduced. We anticipate this mitigation total will come down.

The application references the SDEIS which is available to view in the following location by navigating alphabetically to Derry-Londonderry 13065: https://www.nh.gov/dot/org/projectdevelopment/environment/units/program-management/wetland-applications.htm

Please note that the SDEIS text has not been revised with the most recent wetland impacts, so impact values won't match the application form and text. The SDEIS is currently being revised to incorporate FHWA's comments and the wetland impact changes.

A payment voucher has been processed for this application (Voucher #13065) in the amount of \$10,000 (Fee Cap).

The lead people to contact for this project are Keith Cota, Project Manager, Bureau of Highway Design (271-2731 or Keith.Cota@dot.nh.gov) or Matt Urban, Chief Operations Management Section, Bureau of Environment (271-3226 or matt.urban@dot.nh.gov)

If and when this application meets with the approval of the Bureau, please send the permit directly to Matt Urban, Chief Operations Management Section, Bureau of Environment.

MRU:mru
Enclosures
BOE Original
Town of Derry (4 copies via certified mail)
Town of Londonderry (4 copies via certified mail)
David Trubey, NH Division of Historic Resources
Carol Henderson, NH Fish & Game (via electronic notification)
Maria Tur, US Fish & Wildlife (via electronic notification)
Mark Kern, US Environmental Protection Agency (via electronic notification)
Michael Hicks, US Army Corp of Engineers (via electronic notification)
Kevin Nyhan, BOE (via electronic notification)

S:\Environment\PROJECTS\DERRY\13065\Wetlands\WETAPP - Highway.doc



WETLANDS PERMIT APPLICATION

Water Division/ Wetlands Bureau **Land Resources Management**



RSA/Rule: RSA 482-A	Check the Env-Wt 100-900	status of your applic	cation: <u>www.des.</u>	nh.gov/ones	top	* Miles *
			10 (0,0)	F. 45 - 11 - 11 - 11	Elte No	W 81 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/2 1/
Acrimetatis					Officek, files	
Line Off/y					Jangua	
Sitroc					Installs:	
1. REVIEW TIME: India	cate your Review Time be	elow. To determine r	eview time, refe	r to <u>Guidance</u>	<u>Document A</u> for in	structions.
☑ Standard Rev	ew (Minimum, Minor or N	Major Impact)		Expedited Re	eview (Minimum Imp	pact only)
2. MITIGATION REQUIRED IF mitigation is required a if Mitigation is Required.		on meeting must occ rmine if Mitigation is	cur prior to subm Required Frequ	itting this We	etlands Permit Appli Question	cation. To determine
Mitigation Pre-Ap ☐ N/A - Mitigation	oplication Meeting Date: on is not required	Month: <u>06</u> Day: <u>2</u> 6	<u>0</u> Year: <u>2018</u>			
3. PROJECT LOCATION Separate wetland permi		bmitted for each mu	nicipality that we	tland impact	s occur within.	
ADDRESS: Various					TOWN/CITY:	
TAX MAP:	BLOCK:		LOT:		UNIT:	
USGS TOPO MAP WATER	RBODY NAME: various		□ NA	STREAM W	ATERSHED SIZE: va	rious 🗆 NA
LOCATION COORDINATE	S (If known): 71°19'17.9	52"W 42°53'55.7	85"N	□ Latitude/	Longitude UTM	☐ State Plane
The Towns of Derry Transportation (NHE construction of a ne congestion and imp	OOT), in cooperation with I-	with the Federal I 93 (known as Exi	Highway Adm t 4A) and othe	inistration	(FHWA) are prop	osing the
5. SHORELINE FRONT						
NA This does not have a continuous properties. The continuous properties are a continuous properties are a continuous properties. The continuous properties are a continuous properties are a continuous properties. The continuous properties are a continuous properties are a continuous properties. The continuous properties are a continuous properties are a continuous properties are a continuous properties. The continuous properties are a continuous properties are a continuous properties are a continuous properties are a continuous properties. The continuous properties are a continu	ave shoreline frontage.	SHO	RELINE FRONT	AGE:		
Shoreline frontage is cal straight line drawn between	culated by determining th	ne average of the dis	tances of the ac	tual natural n		frontage and a
6. RELATED NHDES L Please indicate if any of To determine if other Lat	the following permit appl	ications are required	and, if required	the status o	f the application.	
Permi	t Туре	Permit Required	File Numbe	er Perm	nit Application Sta	tus
Alteration of Terrain Peri Individual Sewerage Dis Subdivision Approval Pe Shoreland Permit Per RS	posal per RSA 485-A:2 r RSA 485-A	☐ YES ☐ NO		_ A	APPROVED PE	NDING DENIED NDING DENIED NDING DENIED NDING DENIED
7. NATURAL HERITAG See the Instructions & R			ns to complete a	& b below.		
a. Natural Heritage Bur	eau File ID: NHB 18	- 2355 .				-
b. Designated River date a copy of th	the project is in ¼ miles application was sent to	of: the <u>Local River Mar</u>	nagement Adviso	; and ory Committe	e: Month: Day	: Year:

Irm@des.nh.gov or (603) 271-2147 NHDES Wetlands Bureau, 29 Hazen Drive, PO Box 95, Concord, NH 03302-0095 www.des.nh.gov

8. APPLICANT INFORMATION (Desired permit holder)		-			
LAST NAME, FIRST NAME, M.I.: Cota, Keith		34			
TRUST / COMPANY NAME: NHDOT	MAILING A	DDRESS: 7 H	lazen Driv	/e	
TOWN/CITY: Concord			STATE: N	lH	ZIP CODE: 03302
EMAIL or FAX: Keith.Cota@dot.nh.gov	PHON	E: (603) 271	I-1615		
ELECTRONIC COMMUNICATION: By initialing here:, I hereby au electronically.		S to communi	cate all matte	ers relativ	e to this application
9. PROPERTY OWNER INFORMATION (If different than applica	nt)				
LAST NAME, FIRST NAME, M.I.:					
TRUST / COMPANY NAME:	MAILING A	DDRESS:			
TOWN/CITY:			STATE:		ZIP CODE:
EMAIL or FAX:		PHONE:			
ELECTRONIC COMMUNICATION: By initialing here, I hereby aut electronically.	horize NHDES	S to communic	ate all matte	rs relative	e to this application
10. AUTHORIZED AGENT INFORMATION					
LAST NAME, FIRST NAME, M.I.: Carbonneau, Lee		COMPANY	NAME: Norr	nandea	ıu Associates
MAILING ADDRESS: 25 Nashua Road					
TOWN/CITY: Bedford			STATE: N	Н	ZIP CODE: 03110
EMAIL or FAX: Icarbonneau@normandeau.com	PHONE: (603) 637-11	50		
ELECTRONIC COMMUNICATION: By initialing here <u>LEC</u> , I hereby autho electronically.	rize NHDES to	o communicate	e all matters	relative to	this application
11. PROPERTY OWNER SIGNATURE:					
See the Instructions & Required Attachments document for clarification	on of the belo	ow statemen	ts		
By signing the application, I am certifying that:					
I authorize the applicant and/or agent indicated on this form to upon request, supplemental information in support of this permanental information.	act in my be	ehalf in the pr	ocessing o	f this ap _l	plication, and to furnish
2. I have reviewed and submitted information & attachments outli	ned in the In	structions ar	nd Required	l Attachr	ment document.
3. All abutters have been identified in accordance with RSA 482-					
 I have read and provided the required information outlined in E I have read and understand Env-Wt 302.03 and have chosen to 				ect type	
 I have read and understand Env-Wt 302.03 and have chosen to Any structure that I am proposing to repair/replace was either grandfathered per Env-Wt 101.47. 				Bureau	or would be considered
7. I have submitted a Request for Project Review (RPR) Form (w (SHPO) at the NH Division of Historical Resources to identify the NH Division of Historical Resources the NH Division of Historical Resources to identify the NH Division of Historical Resources the NH Division of Histor	ww.nh.gov/n	hdhr/review) of historical	to the NH	State His	storic Preservation Officer urces while coordinating
with the lead federal agency for NHPA 106 compliance.	n ta inanasti				
8. I authorize NHDES and the municipal conservation commissio9. I have reviewed the information being submitted and that to the	n to inspect	the site of the	e proposed	project.	o and accurate
I understand that the willful submission of falsified or misrepresent Environmental Services is a criminal act, which may result in least to the services are considered.	sented inforn	nation to the	New Hamp	shire De	partment of
11. I am aware that the work I am proposing may require additional	ıl state, local	or federal pe	ermits whicl	n I am re	esponsible for obtaining.
 The mailing addresses I have provided are up to date and app forward returned mail. 	ropriate for r	eceipt of NH	DES corres	pondend	ce. NHDES will not
TATA (A	171, A	Cork	1	1011	118

Print name legibly

Property Owner Signature

Date

MUNICIPAL SIGNATURES

12. CONSERVA	TION COMMISSION SIGNAT	JRE
The signature below certifies that the municipal conset. 1. Waives its right to intervene per RSA 482-A:11; 2. Believes that the application and submitted plans at 3. Has no objection to permitting the proposed work.	accurately represent the propos	
⊢		

Print name legibly

DIRECTIONS FOR CONSERVATION COMMISSION

- 1. Expedited review ONLY requires that the conservation commission's signature is obtained in the space above.
- 2. Expedited review requires the Conservation Commission signature be obtained **prior** to the submittal of the original application to the Town/City Clerk for signature.
- 3. The Conservation Commission may refuse to sign. If the Conservation Commission does not sign this statement for any reason, the application is not eligible for expedited review and the application will be reviewed in the standard review time frame.

	13. TOWN / CITY CLERK SIG	NATURE			
As required by Chapter 482-A:3 (amended 2014), I hereby certify that the applicant has filed four application forms, four detailed plans, and four USGS location maps with the town/city indicated below.					
9					
ightharpoonup					
Town/City Clerk Signature	Print name legibly	Town/City	Date		

DIRECTIONS FOR TOWN/CITY CLERK:

Per RSA 482-A.3,I

- 1. For applications where "Expedited Review" is checked on page 1, if the Conservation Commission signature is not present, NHDES will accept the permit application, but it will NOT receive the expedited review time.
- 2. IMMEDIATELY sign the original application form and four copies in the signature space provided above;
- 3. Return the signed original application form and attachments to the applicant so that the applicant may submit the application form and attachments to NHDES by mail or hand delivery.
- 4. IMMEDIATELY distribute a copy of the application with one complete set of attachments to each of the following bodies: the municipal Conservation Commission, the local governing body (Board of Selectmen or Town/City Council), and the Planning Board; and
- 5. Retain one copy of the application form and one complete set of attachments and make them reasonably accessible for public review.

DIRECTIONS FOR APPLICANT:

1. Submit the single, original permit application form bearing the signature of the Town/ City Clerk, additional materials, and the application fee to NHDES by mail or hand delivery.

Date

14. IMPACT AREA: For each jurisdictional area that wil	I he/has been impacted provide s	guare feet and if	annicable linear feet of impact	
Permanent: impacts that will remain	after the project is complete.			
	o remain (and will be restored to p	re-construction co	onditions) after the project is complete.	
JURISDICTIONAL AREA	Sq. Ft. / Lin. Ft.		TEMPORARY Sq. Ft. / Lin. Ft.	
Forested wetland	129,720	☐ ATF		ATF
Scrub-shrub wetland	3,980	☐ ATF		ATF
Emergent wetland	2,463	☐ ATF		ATF
Wet meadow		☐ ATF		ATF
Intermittent stream	2,619 / 666	ATF		ATF
Perennial Stream / River	24,20 4 / 1,615	☐ ATF	I	ATF
Lake / Pond	1	ATF	1	ATF
Bank - Intermittent stream	1	ATF	1	ATF
Bank - Perennial stream / River	879 / 351	ATF	1	ATF
Bank - Lake / Pond	1	ATF	1	ATF
Tidal water	1	☐ ATF	1	ATF
Salt marsh		☐ ATF		ATF
Sand dune		ATF		☐ ATF
Prime wetland	2,870	ATF		ATF
Prime wetland buffer		☐ ATF		ATF
Undeveloped Tidal Buffer Zone (TBZ)		☐ ATF		☐ ATF
Previously-developed upland in TBZ		☐ ATF		ATF
Docking - Lake / Pond		☐ ATF		ATF
Docking - River		☐ ATF		ATF
Docking - Tidal Water		☐ ATF		☐ ATF
Vernal Pool	50,127	☐ ATF		ATF
TOTAL	216,962 / 2,632		/	
15. APPLICATION FEE: See the li	nstructions & Required Attachmen	ts document for fu	urther instruction	
Minimum Impact Fee: Flat fee				
Minor or Major Impact Fee: Ca				
Permanen	t and Temporary (non-docking) _	216,962 sq.	ft. X \$0.20 = \$43,392.40	
Tempora	ry (seasonal) docking structure: _	sq.	ft. X \$1.00 = _\$	
	Permanent docking structure: _	sq.	ft. X \$2.00 = \$	
Proje	cts proposing shoreline structu	res (including do	ocks) add \$200 = _\$	
			Total = _\$	
The Applica	tion Fee is the above calculated T	otal or \$200, which	chever is greater = \$10,000 (DOT))


Table of Contents

Pag	,e
STANDARD DREDGE AND FILL APPLICATION FORM	ı
EXHIBIT A - LOCATION MAP	5
ATTACHMENT A	Ś
PRIME WETLANDS11	l
EXHIBIT B - NHDOT BUREAU OF ENVIRONMENT CONFERENCE REPORTS 13	3
EXHIBIT C - WATERSHED BOUNDARIES14	ŀ
ENV-WT 900 STREAM CROSSING REQUIREMENTS15	j
MITIGATION17	,
PROPOSED WETLAND MITIGATION)
PHOTOGRAPHS25	j
WETLAND IMPACT PLANS	

Standard Dredge and Fill Application Form

[replace in pdf]

Exhibit A - Location Map



Attachment A

Env-Wt 302.04 Requirements for Application Evaluation - For any major or minor project, the applicant shall demonstrate by plan and example that the following factors have been considered in the project's design in assessing the impact of the proposed project to areas and environments under the department's jurisdiction.

Respond with statements demonstrating:

1. The need for the proposed impact.

The Towns of Derry and Londonderry, working with the Federal Highway Administration (FHWA) and the New Hampshire Department of Transportation (NHDOT) identified several factors demonstrating the need for transportation improvements within the study area, including traffic congestion in downtown Derry, economic vitality, and safety.

Please see Section "2.0 Purpose and Need" in the I-93 Exit 4A Supplemental Draft Environmental Impact Statement (SDEIS) for additional detail.

2. That the alternative proposed by the applicant is the one with the least impact to wetlands or surface waters on site.

Alternatives A & B were the two build alternatives that met the Purpose and Need. One of the key reasons why Alternative A was selected versus Alternative B was related to their combined wetland and stream impacts. Alternative A would impact 4.34 acres of wetland, which includes 1.15 acres of direct vernal pool impacts and will have 2,281 linear feet of stream channel and bank impacts, while Alternative B would impact 10 acres of wetlands including 1.09 acres of direct vernal pool impacts, and impact 1,342 linear feet of streams. Alternative B would have more stream impacts from new crossings on new alignment. Please see "4.12.2 Wetlands and Vernal Pools - Environmental Consequences and 4.14.2 Aquatic Life and Essential Fish Habitat — Environmental Consequences" in the SDEIS for additional detail.

3. The type and classification of the wetlands involved.

The majority of wetland impacts would occur in forested wetlands (4.12 of 4.34 acres). For additional detail please see "4.12.2 Wetlands and Vernal Pools Environmental Consequences" and "Table 4.12-3 Impact Totals by Purpose and Wetland Classification" in the SDEIS.

4. The relationship of the proposed wetlands to be impacted relative to nearby wetlands and surface waters.

Wetlands proposed to be impacted are all in the Beaver Brook watershed. Please see "4.11 Surface Waters and Water Quality" and "4.12 Wetlands and Vernal Pools" for additional detail.

5. The rarity of the wetland, surface water, sand dunes, or tidal buffer zone area.

Wetlands proposed to be impacted are generally typical of wetlands in this part of New Hampshire, with forested wetlands (PFO1E) making up the bulk of wetland impacts. There are 1.15 acres of

vernal pools proposed to be impacted (included in the total), which provide habitat for vernal pool dwelling wildlife species. Please see "4.11 Surface Waters and Water Quality" and "4.12 Wetlands and Vernal Pools" in the SDEIS for additional detail.

6. The surface area of the wetlands that will be impacted.

The proposed project would result in an estimated 4.34 acres of wetland impact, including direct impacts to eight documented vernal pools. Please see "Wetlands and Vernal Pools 4.12.2 Environmental Consequences" in the SDEIS for additional detail.

- 7. The impact on plants, fish and wildlife including, but not limited to:
 - a. Rare, special concern species;
 - b. State and federally listed threatened and endangered species;
 - c. Species at the extremities of their ranges;
 - d. Migratory fish and wildlife:
 - e. Exemplary natural communities identified by the DRED-NHB; and
 - f. Vernal pools.
- a. Based on records held by NHNHB, two species of Special Concern, banded sunfish and redfin pickerel, have been found in Shields Brook, but not in the vicinity of the project crossing. Shields Brook will require a culvert extension, but stream connectivity will be maintained. See "4.14.1 Aquatic Life and Essential Fish Habitat Affected Environment". There are 23 Species of Greatest Conservation Need that could occur within the study area, based on their known habitat preferences and distribution within the state, but their locations are not tracked by NHNHB. See "Table 4.17-3. Species of Greatest Conservation Need that may be Present within the Project Area" in the SDEIS.
- b. An inquiry with the New Hampshire Natural Heritage Bureau indicated that there are recent records of state-threatened black racers in the vicinity of the project area. Proposed mitigation for potential impacts to black racers is discussed in "4.17.2 Threatened and Endangered Species Environmental Consequences Mitigation." No nearby records for any listed turtle species were found in the vicinity of the proposed project. No listed plants have been recorded or observed within the footprint of Alternative A, but the greatest opportunity for any undocumented populations of rare plants to be affected by the proposed Project is along portions of the Project that cross or are aligned with transmission line ROW. See "4.17.2 Threatened and Endangered Species Environmental Consequences" in the SDEIS for more details.

The only federally listed species potentially present within the Project area is the federally listed as threatened northern long-eared bat (NLEB; *Myotis septentrionalis*). This species is also state-listed as threatened. This tree-roosting bat uses forested habitats during its active season from April 15 – October 31. The Project has the potential to affect this species via tree clearing, which could reduce roosting habitat or cause direct mortality if an occupied roost tree is felled when bats are present. Therefore, a survey compliant with USFWS' 2016 *Range-wide Indiana Bat Summer Survey Guidelines* (Guidelines) (USFWS, 2016), which are also applicable to summer survey for NLEB, was conducted, and this species was determined not to be present. Appendix M of the SDEIS contains a full

description of the survey and results.

- c. Species at the extremity of their ranges are generally included in lists of Species of Special Concern or Species of Greatest Conservation Need. See "a." above.
- d. The Project area is characterized by substantial development, but there is one large block of forest that will be fragmented by the Project. This could have an impact on several migratory forestnesting birds (e.g., wood thrush, scarlet tanager, red-eyed vireo, and broad-winged hawk) that are sensitive to the fragmentation and edge effects that the road would create. Habitat suitability for them in the remaining forest area would be reduced. Stream connectivity will be maintained and no impacts to the catadromous American eel is expected. See "4.16.2 Plant Communities and Wildlife Environmental Consequences" and "4.14.1 Aquatic Life and Essential Fish Habitat Affected Environment" in the SDEIS for additional details.
- e. No exemplary natural communities will be directly affected by the proposed Project.
- f. The Project would impact a total 4.34 acres of wetlands, including 1.15 acres of vernal pool habitat. A total of eight vernal pools would be directly impacted by the project. Please see "4.12.2 Wetlands and Vernal Pools Environmental Consequences Vernal Pool Impacts" in the SDEIS for additional detail.
- 8. The impact of the proposed project on public commerce, navigation and recreation.

In Derry, current constraints related to through traffic are a concern to the accessibility of businesses downtown. In Londonderry, a large tract of undeveloped land on the east side of I-93 currently has poor highway access and is the subject of the Town's Woodmont Commons Planned Unit Development (PUD) Master Plan to attract regionally significant business opportunities.

Under the proposed Project, approximately 41.45 acres of new ROW would be required, and these takes would include 14 residential acquisitions and 25 business displacements. In addition to compensation for property acquisition, relocation assistance would be provided to residential, non-profit, and business owners displaced by the Project in conformance with the Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, as amended. See "4.7.2 Socioeconomics - Environmental Consequences – Mitigation" in the SDEIS for additional details. Implementation of the proposed project would provide direct Interstate access to commercial and industrial lands and be compatible with existing and future commercial and industrial uses. Please see "2.2.2 Economic Vitality" and "4.3.2 Land Use, Zoning, and Public Policy – Environmental Consequences" for additional detail.

No navigable waters are crossed by the Project.

There will be a very minor impact to Ryder Field which will not interfere with the recreational use of the property. See "7.4 Potential for Use and Impacts on Section 4(f) Resources" in the SDEIS for additional details.

9. The extent to which a project interferes with the aesthetic interests of the general public. For example, where an applicant proposes the construction of a retaining wall on the bank of a lake, the applicant shall be required to indicate the type of material to be used and the

effect of the construction of the wall on the view of other users of the lake.

The majority of the proposed Project corridor includes existing roads located in highly developed residential and commercial/industrial areas. Therefore, in most areas of the proposed project corridor, the existing traffic volumes, along with the type of development and its density, make for an environment that is not particularly sensitive from a visual perspective.

Between I-93 and Franklin Street Extension, the proposed project corridor would be constructed in an undeveloped area of land. From a visual perspective, the area represents a visually pleasing landscape of woodlands and wetlands. However, there is also abundant evidence of past and ongoing illegal dumping activities, as well as all-terrain vehicle usage, which detracts from the overall visual experience.

Please see "4.6.2 Visual Resources – Environmental Consequences" in the SDEIS for additional detail on aesthetic impacts of the proposed project.

10. The extent to which a project interferes with or obstructs public rights of passage or access. For example, where the applicant proposes to construct a dock in a narrow channel, the applicant shall be required to document the extent to which the dock would block or interfere with the passage through this area.

Under the proposed project, there would be a reduction in trips on east-west roadways including NH 102 and NH 28. The creation of a new parallel route to NH 102 would create a shift in traffic patterns through downtown Derry. The Project will not impact public access to, or passage along, public waters. Please see "4.2.2 Traffic and Transportation – Environmental Consequences" in the SDEIS for additional detail.

11. The impact upon abutting owners pursuant to RSA 482-A:11, II. For example, if an applicant is proposing to rip-rap a stream, the applicant shall be required to document the effect of such work on upstream and downstream abutting properties.

Design details including scour stone and riprap have not yet been designed, but will be included in final design plans. Impacts to abutting property owners will be avoided and minimized during construction through the use of appropriate construction BMPs.

12. The benefit of a project to the health, safety, and well being of the general public.

Part of the purpose of the Project is to improve the safe and efficient movement of people, goods, and services between I-93 and the towns served by NH 102, specifically Derry and Londonderry, that are immediately adjacent to I-93 Exit 4; and providing an alternative route to the Interstate system for traffic using NH 102 to and from the east, thus removing a large volume of through traffic from the heavily congested downtown Derry street network. Reducing traffic congestion on the Derry street network will improve safety by allowing more opportunities for vehicles to find gaps in traffic to make safer traffic turning movements into and across traffic. Reduced traffic will also make it safer for bicyclists and pedestrians to travel. Contiguous sidewalks are being provided throughout the project to improve safety and four to five foot wide shoulders are being provided for bicyclists.

In addition, the profile (vertical alignment) of Tsienneto Road east of Scenic Drive is proposed to be revised to provide a less abrupt curvature to make it meet minimum AASHTO stopping sight distance standards. Also the intersection sight distance from Scenic Drive is proposed to be improved to meet the posted speed standard.

13. The impact of a proposed project on quantity or quality of surface and ground water. For example, where an applicant proposes to fill wetlands the applicant shall be required to document the impact of the proposed fill on the amount of drainage entering the site versus the amount of drainage exiting the site and the difference in the quality of water entering and exiting the site.

The proposed project includes development of new roadway in undeveloped areas or areas with non-roadway current land use as well as redevelopment of existing roadway that would result in new impervious surface within Upper Beaver Brook watershed. The addition of new impervious roadway surfaces that contribute stormwater runoff to surface waters has the potential to add new TSS and nutrient loads to the watershed. Please see "4.11.2 Surface Waters and Water Quality — Environmental Consequences" in the SDEIS for additional detail.

The proposed project footprint overlaps seven wellhead protection areas. However, several of these public wells are located near each other and therefore share largely overlapping WHPAs that occupy much of the same land area. Please see "4.13.2 Groundwater – Environmental Consequences" in the SDEIS for additional detail.

14. The potential of a proposed project to cause or increase flooding, erosion, or sedimentation.

The primary area of impact for the proposed project would be on the floodplain for Shields Brook. The proposed project would cross the Shields Brook floodplain near the existing Folsom Road/Madden Road crossing. Detailed hydraulic analyses will be completed during final design to avoid and/or minimize impacts on the floodway, and in particular to avoid raising the base flood elevation. Please see "4.15.2 Floodplains – Environmental Consequences" in the SDEIS for additional detail.

15. The extent to which a project that is located in surface waters reflects or redirects current or wave energy which might cause damage or hazards.

Several surface waters in the project area may be affected by the construction and maintenance of the proposed roadway. However, none are tidal and current/wave energy is not anticipated to be impacted by any alternative. Please see "4.11 Surface Waters and Water Quality" for additional detail.

16. The cumulative impact that would result if all parties owning or abutting a portion of the affected wetland or wetland complex were also permitted alterations to the wetland proportional to the extent of their property rights. For example, an applicant who owns only a portion of a wetland shall document the applicant's percentage of ownership of that wetland and the percentage of that ownership that would be impacted.

Cumulative effects (including direct impacts of the proposed project, indirect impacts attributable to the project, and actions by others) are documented in detail in Chapter 5 of the SDEIS. Given the uncertainty associated with forecasting future land use changes, potential cumulative impacts to streams, wetlands and vernal pools are expressed as a range (minimum and maximum impacts). The Land Use Scenarios Technical Report provides the basis for the land development assumptions and this report was provided for review to all the participating and cooperating agencies during the SDEIS process.

17. The impact of the proposed project on the values and functions of the total wetland or wetland complex.

Functions and values of each affected wetland were evaluated and are summarized **in** Table 1 of Appendix J of the SDEIS, and the impacts to wetlands are discussed in "4.12.2 Wetlands and Vernal Pools – Environmental Consequences" in the SDEIS.

18. The impact upon the value of the sites included in the latest published edition of the National Register of Natural Landmarks, or sites eligible for such publication.

Not applicable. No listed sites from the National Register of Natural Landmarks occur within Rockingham County, NH.

19. The impact upon the value of areas named in acts of congress or presidential proclamations as national rivers, national wilderness areas, national lakeshores, and such areas as may be established under federal, state, or municipal laws for similar and related purposes such as estuarine and marine sanctuaries.

No national rivers, wilderness areas, national lakeshores or such areas are within or adjacent to the study area.

20. The degree to which a project redirects water from one watershed to another.

All drainage from the project is currently within and will remain within the Upper Beaver Brook watershed (Level 12 Hydrologic Unit 010700061025).

Additional Comments

None

Prime Wetlands

The project currently proposes to impact 2,870 square feet of Prime Wetland B-12, north of Tsienneto Road and west of the intersection with NH 102. The impacts will be related to the replacement of two side by side culverts under Tsienneto Road. Under current conditions, the culverts are undersized and result in frequent flooding of the adjacent properties. A stream crossing with a weir is proposed to maintain water elevations in the prime wetland while allowing additional flow capacity under Tsienneto Road.

STANDARD DREDGE AND FILL WETLAND APPLICATION

In accordance with Env-Wt 703, Prime Wetlands Permit Process, the following will be demonstrated in a subsequent submission to NHDES:

- (1) There will be no significant net loss of values set forth in RSA 482-A:1;
- (2) The project is consistent with the purpose specified in RSA 482-A:1;
- (3) The project could not be relocated to avoid impacts on prime wetlands without either reducing the public value of the project, or negatively affecting the public health or safety;
- (4) The project's impacts on prime wetlands are the minimum practical without either reducing the public value of the project, or negatively affecting the public health or safety; and
- (5) The project incorporates appropriate and practicable compensatory mitigation for each of the wetland functions and values of RSA 482-A:1, and each of the functions and values ranked by the municipality, that are impacted by the project. The mitigation proposed shall be appropriate in terms of matching the proposed benefit given the relative harm of the project. The mitigation shall be practicable given the technology available at the time of this application.

Exhibit B - NHDOT Bureau of Environment Conference Reports


The project was reviewed on the following dates:

5/28/1997	3/17/1999	6/16/1999	10/20/1999	11/17/1999	8/16/1999	9/20/2000
7/18/2001	8/17/2005	3/15/2006	5/16/2007	1/20/2016	2/17/2016	10/19/2016
4/18/2018	6/20/2018					

Minutes can be found at the link below under Derry-Londonderry 13065:

https://www.nh.gov/dot/org/projectdevelopment/environment/units/projectmanagement/nracrmeetings.htm

Exhibit C - Watershed Boundaries



14

Env-Wt 900 Stream Crossing Requirements

As currently proposed, the project will incur impacts at 9 stream locations. Stream crossings and stream impacts are described in Section 4.14.2, "Aquatic Life and Essential Fish Habitat, Environmental Consequences" in the SDEIS. Stream crossings are summarized in Table 8. Hydraulic analyses are underway for all stream crossings in the project area and Env-Wt 900 et. seq. will be addressed in detail in a subsequent submission to the NHDES.

Table 1 Exit 4A Stream Impact Summary

Cross- ing	Flow Regime ^a	Tier	Water- shed Size (Acres) b	Existing Crossing	Location	Activity Description	Linear Feet of Stream/ Bank Impact
1	Per.	2	269	No crossing	New access ramp W of I-93 at southern Exit 4A interchange -71°20'56" 42°53'4"	Relocate perennial stream channel. Portions of channel already impacted from I-93 construction.	1,095
2	Per. Shields Brook	3	3,767	72" CMP	N. High St - between Ferland Drive and Franklin St -71°19'54 42°53'23"	Extend existing culvert crossing to the north to accommodate connector road.	447
3	Int.	1	148	15" HDPE	Tsienneto Road - Approx. 200 ft west of Scenic Drive -71°18'26" 42°54'27"	Extend culvert to accommodate road widening.	38
4	Int.	1	30	15" unknown material culvert	Tsienneto Road - between Scenic Drive and Jeff Lane -71°18'21" 42°54'31"	Extend culvert to accommodate road widening.	35
5	Per. Un- named	3	850	30" and 36" CMPs	Tsienneto Road - 250 ft west of NH 102 -71°18'10 42°54'37	Extend culvert to accommodate road widening.	73
7	Int.	1	35	24" RCP (existing is two pipes, one under SB and another under NB)	New access ramp - E of I-93 at southern interchange -71°20'56 42°53'11	Extend culvert under new I-93 northbound off-ramp and southbound on-ramp.	177

Cross- ing	Flow Regime ^a	Tier	Water- shed Size (Acres) b	Existing Crossing	Location	Activity Description	Linear Feet of Stream/ Bank Impact
8	Int.	1	19	None	New alignment - 500 ft E of I-93 71°20'51" 42°53'15"	Construct new stream crossing/relocate stream for connector road.	291
11	Eph. ^a	1	Un- deter- mined ^d	None	New alignment - 300 ft N of Madden Drive -71°20'9" 42°53'21"	Stream relocation/impact.	77
70	Int.	1	65	None	New access ramp W of I-93 at southern Exit 4A interchange -71°20'56" 42°53'4"	Stream relocation/impact.	48

Flow regime based on observation and watershed size. In the absence of long term monitoring for streams in the project area, streams with watersheds smaller than 200 acres were assumed to be intermittent, and larger than 200 acres were assumed to be perennial. Ephemeral streams had no measurable watershed and had physical characteristics meeting the NHDES definition of ephemeral streams.

- Watershed sizes based on Streamstats basin delineation: https://streamstats.usgs.gov/ss/.
- ^c Linear disturbance estimates based on preliminary design information.
- Unable to determine watershed size using Streamstats.
- The upstream portion of Crossing #5 is mapped as prime wetland which will be affected by the improvements to Tsienneto Road.

Mitigation

Mitigation plans have not been finalized at this conceptual design stage. NHDOT is committing to working with the Towns of Londonderry and Derry to evaluate local stream crossing locations that would qualify for improvement funding as part of the Stream Passage Improvement Program (SPIP) agreement with NHDES to upgrade culverts within the Beaver Brook watershed.

Other than culvert improvements to be made through the SPIP, mitigation will primarily be a payment to the Aquatic Resource Mitigation (ARM) fund. Proposed mitigation for previous iterations of the Exit 4A project had incorporated elements of stream restoration, vernal pool creation, and land preservation. The total in-lieu fee recommended for this project is estimated at \$2,819,054.83 as summarized in Table 2.

Table 2. Exit 4A Proposed In-Lieu Fee Summary

Resource	In Lieu Fee Estimate	Assumptions
Wetlands		Includes vernal pools as forested wetlands in
(including		accordance with 2016 USACE Mitigation
riverbanks)	\$953,774.91	Guidance.
		Mitigation for secondary "Edge Effects" are
Secondary Impacts		calculated as recommended in the 2016 USACE
"Edge Effects"	\$395,765.44	Mitigation Guidance.
		Vernal pool additional mitigation based on
		ratios recommended in 2016 USACE Mitigation
Vernal Pools	\$835,701.36	Guidance, based on quality of vernal pools.
		Calculated for impacts to channels and banks
Streams	\$633,813.12	using the 2018 In-Lieu Fee Calculator.
TOTAL	\$2,819,054.83	

Proposed Wetland Mitigation

Wetland impacts for the Exit 4A Project as currently proposed are listed in Table 3.

Table 3 Proposed Wetland Impacts

Cowardin	Acreage
PFO (forested)	2.98
PSS (scrub-shrub)	0.09
PEM (emergent)	0.12
Vernal Pools	1.15
Total	4.34

In-Lieu fee Estimated Payment for Wetland Impacts

Using the 2018 In-Lieu Fee Calculator, the in-lieu fee for wetland impacts, not counting square footage of streams but counting vernal pools as forested wetlands, is estimated at \$953,774.91.

Table 4 In-Lieu Fee Calculation for Direct Wetland Impact

NHDES AQUATIC RESOURCE MITIGATION FUND WETLAND PAYMENT CALCULATION ***INSERT AMOUNTS IN VELLOW CELLS***

)	SERT AMOUNTS IN YELLOW CELI				
1	Convert square feet of im	pact to acres:			
INSERT SQ FT OF IMPACT	Square feet of impact = 189,183				
		43560.00			
	Acres of impact =	4.3430			
·					
2	Determine acreage of wet	land construction:			
	Forested wetlands:	6.5146			
	Tidal wetlands:	13.0291			
	All other areas:	6.5146			
3	Wetland construction cos	t:			
	Forested wetlands:	\$581,167.09			
	Tidal Wetlands:	\$1,162,334.19			
	All other areas:	\$581,167.09			
4	Land acquisition cost (See	e land value table):			
INSERT LAND VALUE FROM TABLE WHICH APPEARS TO	Town land value:	32,795			
THE LEFT. (Insert the amount	Forested wetlands:	\$213,645.33			
do not copy and paste.)	Tidal wetlands:	\$427,290.66			
	All other areas:	\$213,645.33			
5	Construction + land costs				
	Forested wetland:	\$794,812.43			
	Tidal wetlands:	\$1,589,624.85			
	All other areas:	\$794,812.43			
6	NHDES Administrative cos	**			
	Forested wetlands:	\$158,962.49			
	Tidal wetlands:	\$317,924.97			
	All other areas:	\$158,962.49			
*******	TOTAL ARM PAYMENT****	******			
	Forested wetlands:	\$953,774.91			
	Tidal wetlands:	\$1,907,549.82			
	All other areas:	\$953,774.91			

Secondary Impacts (Edge Effects)

The US Army Corps of Engineers 2016 Mitigation guidance also provides ratios for temporary fill, permanent conversion (forested to emergent) and secondary impact edge effects. The guidelines recommend that a portion of the standard amount of mitigation that would be required if a wetland were directly impacted should be added to the total if the project is within the "Impact Zone" of the project. The size of the Impact Zone varies by wetland type, and Impact Zones are broken into two types, depending on proximity to the project, with "High Level Impact Zone" being the closer portion, and requiring more mitigation than the rest of the impact zone.

Temporary fill and permanent conversion of wetland type are unlikely to be significant in this project. Secondary Impact Edge Effects are tabulated in Table 5. Secondary Impact Edge Effects were tabulated for areas of new alignment, road widening, and around proposed stormwater treatment areas.

Table 5. USACE Recommended Secondary Impact Edge Effects (from Table C2, Page 58 in 2016 USACE Guidance)

Wetland Type	Impact Zone ^a	Acreage in Impact Zone (30% Design)	% of Standard Amount	Acreage to be mitigated
Palustrine	25	0.14	25%	0.04
Emergent	75	0.23	10%	0.02
Scrub	50	0.16	25%	0.04
Shrub	100	0.69	10%	0.07
Forested	50	3.48	25%	0.87
	150	9.31	10%	0.93
			Total	1.80 ^b

Notes – a USACE identifies "High level impact zones" and "remainder of impact zone" for emergent, scrub shrub, and forested wetlands. The amount of mitigation required is a percentage of what would be required for direct impacts.

b Secondary impact edge effects have been refined since the June 20, 2018 Natural Resource Agency meeting.

In-Lieu fee Estimated Payment for Secondary Edge Effect Impacts

Secondary Impact Edge Effects add an estimated \$395,765.44 to the fee.

Table 6. In-Lieu Fee Calculation Secondary Impacts

NHDES AQUATIC RESOURCE MITIGATION FUND WETLAND PAYMENT CALCULATION ***INSERT AMOUNTS IN YELLOW CELLS*** 1 Convert square feet of impact to ac

INSERT	AMOUNTS IN YELLOW CELLS****				
1	Convert square feet of impact to acres:				
INSERT SQ FT OF IMPACT	Square feet of impact =	78,501			
		43560.00			
	Acres of impact =	1.8021			
2	Determine acreage of wetla	and construction:			
	Forested wetlands:	2.7032			
	Tidal wetlands:	5.4064			
	All other areas:	2.7032			
3	Wetland construction cost	:			
	Forested wetlands:	\$241,153.18			
	Tidal Wetlands:	\$482,306.36			
	All other areas:	\$241,153.18			
4 NSERT LAND VALUE FROM	Land acquisition cost (See				
ABLE WHICH APPEARS TO	Town land value:	32,795			
HE LEFT. (Insert the amount	Forested wetlands:	\$88,651.36			
lo not copy and paste.)	Tidal wetlands:	\$177,302.71			
	All other areas:	\$88,651.36			
5	Construction + land costs:				
	Forested wetland:	\$329,804.54			
	Tidal wetlands:	\$659,609.07			
	All other areas:	\$329,804.54			
6	NHDES Administrative cos				
1	Forested wetlands:	\$65,960.91			
	Tidal wetlands:	\$131,921.81			
	All other areas:	\$65,960.91			
******	TOTAL ARM PAYMENT********				
	Forested wetlands:	\$395,765.44			
	Tidal wetlands:	\$791,530.89			
	All other areas:	\$395,765.44			

¹ The equalized land valuation for Derry and Londonderry are the same in the 2018 in-lieu fee calculator: \$32,795/acre.

Vernal Pool Mitigation

The 2016 USACE Mitigation Guidance provides recommendations for in-lieu payments for vernal pool impacts with a multiplier based on the quality of the vernal pool. Vernal pool quality is evaluated using the USACE's "Vernal Pool Characterization" form² that provides a scoring system for low, medium, and high quality vernal pools based on the characteristics of the vernal pool itself and of the surrounding landscape. For Exit 4A, using the USACE scoring system in the 2013 Vernal Pool Characterization Form, there are 2 high quality and 6 medium quality vernal pools proposed to be impacted. Therefore, recommended mitigation under the USACE Guidance would be as provided in Table 9.

In-Lieu Fee Estimated Payment for Vernal Pool Impacts

The 2016 USACE Guidance recommends a ratio pattern of 1:1 (low quality): 1:3 (medium quality): 1:5 (high quality) for in-lieu fee calculations. Using this guidance, the total area to be mitigated would be 169,561 square feet, or 3.89 acres.

Table 7. USACE Recommended In- Lieu Fee Multiplier for Vernal Pool Impacts (from USACE 2016 Mitigation Guidance, Page 95)

		timegation C	
Vernal Pool Characterization	Recommended ratio for preservation	Square feet of impact proposed	Square Feet Impact x USACE multiplier
Medium	1:3	41,299	123,897
High	1:5	8,279	41,395
Low	1:1	471	471
	TOTAL	50,049	165,763

In addition to the in-lieu fee payment already calculated for the vernal pools under wetland impacts (1.15 acres forested wetland). The ARM fund payment for the additional 3.89 acres is estimated at \$835,701.36 as detailed in Table 8.

 $^{{}^2\}underline{http://www.nae.usace.army.mil/Portals/74/docs/regulatory/StateGeneralPermits/NEGP/VPCharacterizationFormDRAFT.pdf}$

Table 8 In-Lieu Fee Calculation for Vernal Pools

NHDES AQUATIC RESOURCE MITIGATION FUND WETLAND PAYMENT CALCULATION ***INSERT AMOUNTS IN YELLOW CELLS***

1	Convert square feet of impact to acres:				
INSERT SQ FT OF IMPACT	Square feet of impact =	165,763			
		43,560			
	Acres of impact =	3.8054			
2	Determine acreage of wet	land construction:			
	Forested wetlands:	5.7081			
	Tidal wetlands:	11.4162			
	All other areas:	5.7081			
3	Wetland construction cos	t:			
	Forested wetlands:	\$509,220.91			
	Tidal Wetlands:	\$1,018,441.82			
	All other areas:	\$509,220.91			
4	Land acquisition cost (See land value table):				
SERT LAND VALUE FROM ABLE WHICH APPEARS TO	Town land value:	32795			
HE LEFT. (Insert the amount	Forested wetlands:	\$187,196.89			
o not copy and paste.)	Tidal wetlands:	\$374,393.77			
	All other areas:	\$187,196.89			
5	Construction + land costs	0			
	Forested wetland:	\$696,417.80			
	Tidal wetlands:	\$1,392,835.59			
	All other areas:	\$696,417.80			
6	NHDES Administrative cos	st:			
	Forested wetlands:	\$139,283.56			
	Tidal wetlands:	\$278,567.12			
	All other areas:	\$139,283.56			
*******	TOTAL ARM PAYMENT****	****			
	Forested wetlands:	\$835,701.36			
	Tidal wetlands:	\$1,671,402.71			
	All other areas:	\$835,701.36			

Stream Mitigation


NHDES Stream Mitigation

Linear feet of stream and bank impacts are provided in the wetland application. Stream crossing 5, downstream of the Prime Wetland on Tsienneto Road, is assumed to be self-mitigating. All other linear feet of stream impact were included in the in-lieu fee calculation. Stream mitigation funding may be further reduced by the SPIP.

NHDES	AQUATIC RESOURCE MITIC	GATION FUND
INSERT LINEAR FEET		
OF IMPACT on BOTH BANKS		
AND CHANNEL	Right Bank	26
	Left Bank	8
	Channel	2,20
	TOTAL IMPACT	2,55
	Stream Impact Cost:	\$528,177.6
	NHDES Administrative cost:	
		\$105,635.5
*****	TOTAL ARM FUND STREAM PA	
		\$633,813.1

Photographs

Photographs of wetlands proposed to be impacts can be found in Appendix J of the SDEIS.



TOWNS OF LONDONDERRY & DERRY
COUNTY OF ROCKINGHAM
SCALE: 1" = 1000'


FOR CONSTRUCTION AND ALIGNMENT DETAILS - SEE CONSTRUCTION PLANS


1000 0 1000 2000 SCALE IN FEET **September 25, 2018**

	THE STATE ON NEW HAMPSHIRDEPARTMENT OF RANSPORTATION OF THE PROPERTY OF THE PR
RECOMMENDED FOR APPROVAL:	
DIRECTOR OF PROJECT DEVELOPMENT	DATE
DIRECTOR OF PROJECT DEVELOPMENT APPROVED:	DATE
APPROVED:	ER DATE
APPROVED: ASSISTANT COMMISSIONER AND CHIEF ENGINE	DATE DATE

APPROVED:	
DIVISION ADMINISTRATOR	DATE

FEDERAL PROJECT NO.	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
IM-0931(201)	13065	1	25





NUMBER CLASSIFICATION LOCATION PERMANENT IMPACTS N.H.W.B. & TEMPORARY	WETLAND	WETLAND	LOCATION			AREA				
NAME STATE			LOCATION		PERMANEN				1	
SS SS U					N.H.W.B. & A.C.O.E.	- · · · · · · · · · · · · · · · · · · ·	CHANNEL		TOWN	COMME
Signature Sign						15	<u> </u>		1	
S1	-			51-	SF	<u></u>	LF] SF	 , 	
Sil	S1	RSUBS	Δ		805		36			Accessors accessors assess assess assess assessed a
1.4 PFO1/2E C 265 L L	[·ę·····	
1.4 PFO1/2E D 45 L L		THE RESERVE AND ADDRESS OF THE PARTY OF THE			CONTRACTOR AND	***************************************			· · · · · · · · · · · · · · · · · · ·	* ***** ** ***** **** **** **** **** ****
14	,									
15	14	TITTO THE ANIMAL WARRANT AND ANIMAL ANIMAL AND ANIMAL AND ANIMAL AND ANIMAL AND ANIMAL AND ANIMAL A					1			
15	15	***************************************							······	
14	VP2	VP	G		7236				L	
15	15	PFO1E	Н		1324				L	
VPB	14	PFO1/2E	1		3538				L	
15	16	PFO1E	J		2336				L	
STO RSSS N	VP3	VP	K		6413				L	
S70			***************************************						L	
14	the state of the second state of the second	THE RESERVE THE PARTY OF THE PA	·						L	
14			·····				48		÷	
14					The second secon				·	
14									·	
16		***	***						L	
VP4		***************************************							L	
15	CONTRACTOR OF THE PARTY OF THE									
16										
17	Caleston Company of the water of the comp	THE CONTRACT OF A SECTION ASSESSMENT								
ST			-			***************************************				
17	THE RESIDENCE AND ADDRESS OF THE	to development your new new contract and approximation to a							L L	
S7	***************************************						74			******
S7	Carrena con contra co la contra								L	****
13	h								L	
66	processor comments of comments	**************************************					72			
11		****								
11	***************************************									
For							-			
11										
11										
19		······································								
VP42 VP	A		****				 			
18							 			
19	and the same of th	A 100 AN AL			The state of the s					
S8 R4SB5 AM 1232 291 L 20 PFOIE AN 273 L L 20 PFOIE AN 273 L L 20 PFOIE AN 257 L L VP46 VP AQ 78 L L VP46 VP AQ 78 L L 22 PFOIE AR 106 L L 68 PFOIE AS 117 L L 24 PFOIE AS 117 L L 24 PFOIE AV 5 L L 24 PFOIE AW 452 L L 24 PFOIE AW 2597 L L 24 PFOIE AY 2597 L L 24 PFOIE AZ 118 L L VP8 VP BB	***************************************	······		-		· · · · · · · · · · · · · · · · · · ·				
20	handstandership i trans to broom	and the second s			the same of the common department and the company		201		L	
20							291		_ <u> </u>	
21										
VP46 VP AQ 78 L 22 PFO1E AR 106 L 68 PFO1E AS 117 L 24 PFO1E AT 166 L VP6 VP AU 13296 L L 24 PFO1E AV 5 L L 24 PFO1E AW 452 L L 24 PFO1E AX 46 L L 24 PFO1E AX 46 L L 24 PFO1E AY 2597 L L 24 PFO1E AZ 118 L L 35 PFO1E BA 1181 L L VP8 VP BB 9510 L L 35 PFO1E BC 21 L L 35 PFO1E BE 5 L L 35 PFO1E<										
22										
68 PFO1E AS 117 L L 24 PFO1E AT 166 L L VP6 VP AU 13296 L L 24 PFO1E AV 5 L L 24 PFO1E AW 452 L L 24 PFO1E AX 46 L L 24 PFO1E AY 2597 L L 24 PFO1E AZ 118 L L 35 PFO1E BA 1181 L L 35 PFO1E BC 21 L L 35 PFO1E BC 21 L L 35 PFO1E BC 21 L L 35 PFO1E BE 5 L L 35 PFO1E BF 489 L L 64 PFO1E BG										
24 PFO1E AT 166 L VP6 VP AU 13296 L 24 PFO1E AV 5 L 24 PFO1E AW 452 L 24 PFO1E AX 46 L 24 PFO1E AY 2597 L 24 PFO1E AZ 118 L 35 PFO1E BA 1181 L VP8 VP BB 9510 L 35 PFO1E BC 21 L 35 PFO1E BC 21 L 35 PFO1E BC 5 L 35 PFO1E BC 5 L 35 PFO1E BF 489 L 64 PFO1E BF 489 L 64 PFO1E BG 75 D 39 PEMIF BH 4562										
VP6 VP AU 13296 L 24 PFO1E AV 5 L 24 PFO1E AW 452 L 24 PFO1E AX 46 L 24 PFO1E AY 2597 L 24 PFO1E AZ 118 L 35 PFO1E BA 1181 L VP8 VP BB 9510 L 35 PFO1E BC 21 L 35 PFO1E BC 21 L 35 PFO1E BD 301 L 35 PFO1E BE 5 L 35 PFO1E BF 489 L 464 PFO1E BG 75 D 39 PEMIF BH 4562 D 511 R48B5 BI 77 77 D 40 PSS1E BK		we are to the production of the contract the con-	**** *****							
24 PFO1E AV 5 L 24 PFO1E AW 452 L 24 PFO1E AX 46 L 24 PFO1E AY 2597 L 24 PFO1E AZ 118 L 35 PFO1E BA 1181 L VP8 VP BB 9510 L 35 PFO1E BC 21 L 35 PFO1E BC 21 L 35 PFO1E BD 301 L 35 PFO1E BF 489 L 44 PFO1E BF 489 L 52 BANK BI 77 77 D 40 PSS1E BJ 816 D 52 BANK BL 477 215 D										
24 PF01E AW 452 IL IL <td< td=""><td>NAME OF A PERSON OF A PARTY OF THE PARTY OF</td><td></td><td></td><td></td><td></td><td></td><td> </td><td></td><td></td><td></td></td<>	NAME OF A PERSON OF A PARTY OF THE PARTY OF									
24 PF01E AX 46 L L 24 PF01E AY 2597 L L 24 PF01E AZ 118 L L 35 PF01E BA 1181 L L VP8 VP BB 9510 L L 35 PF01E BC 21 L L 35 PF01E BD 301 L L 35 PF01E BE 5 L L 35 PF01E BF 489 L L 64 PF01E BG 75 D D 39 PEM1F BH 4562 D D 511 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D				-				1-1-1-1		
24 PF01E AY 2597 Image: Control of the property of				-						
24 PFO1E AZ 118 L L 35 PFO1E BA 1181 L L VP8 VP BB 9510 L L 35 PFO1E BC 21 L L 35 PFO1E BD 301 L L 35 PFO1E BE 5 L L 35 PFO1E BF 489 L L 64 PFO1E BG 75 D D 39 PEMIF BH 4562 D D 511 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D 52 BANK BL 477 215 D D					*					
35 PFO1E BA 1181 L L VP8 VP BB 9510 L L 35 PFO1E BC 21 L L 35 PFO1E BD 301 L L 35 PFO1E BE 5 L L 35 PFO1E BF 489 L L 64 PFO1E BG 75 D D 39 PEM1F BH 4562 D D 511 R4SB5 BI 77 77 D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D 52 BANK BL 477 215 D D					The same of the part of the part of					
VP8 VP BB 9510 L 3S PF01E BC 21 L 3S PF01E BD 301 L 3S PF01E BE 5 L 3S PF01E BF 489 L 64 PF01E BG 75 D 39 PEMIF BH 4562 D 511 R4SB5 BI 77 77 D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D 52 BANK BL 477 215 D	P									
35 PF01E BC 21 L L 35 PF01E BD 301 L L 35 PF01E BE 5 L L 35 PF01E BF 489 L L 64 PF01E BG 75 D D 39 PEM1F BH 4562 D D 511 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D D 41 PSS1E BK 141 D D D 52 BANK BL 477 215 D D										
35 PF01E BD 301 L L 35 PF01E BE 5 L L 35 PF01E BF 489 L L 64 PF01E BG 75 D D 39 PEM1F BH 4562 D D 511 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D D 41 PSS1E BK 141 D D D 52 BANK BL 477 215 D D D									***************************************	
35 PF01E BE 5 L L 35 PF01E BF 489 L L 64 PF01E BG 75 D D 39 PEM1F BH 4562 D D 511 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D D 41 PSS1E BK 141 D D D 52 BANK BL 477 215 D D			OF THE PARTY AND ADDRESS OF THE PARTY AND ADDR					1		
35 PF01E BF 489 L 64 PF01E BG 75 D 39 PEM1F BH 4562 D 511 R4SB5 BI 77 77 D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D 52 BANK BL 477 215 D							 			
64 PFO1E BG 75 D D 39 PEM1F BH 4562 D D S11 R4SB5 BI 77 77 D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D S2 BANK BL 477 215 D D			A PROCESS IN COMPANY				 			
39 PEMIF BH 4562 D S11 R4SB5 BI 77 77 D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D S2 BANK BL 477 215 D D										
S11 R4SB5 BI 77 77 D D 40 PSS1E BJ 816 D D 41 PSS1E BK 141 D D S2 BANK BL 477 215 D D						.,	+			
40 PSSIE BJ 816 D 41 PSSIE BK 141 D S2 BANK BL 477 215 D	·						77		·····	
41 PSS1E BK 141 D S2 BANK BL 477 215 D	PH-1111									
S2 BANK BL 477 215 D							 			
				477	7-17	215	1			
					7412		306			
41 PFO1E BN 6165 D							230			
S2 BANK BO 72 32 D				72	0103	23				

				WETL	AND IMPACT SU	MMARY		_		
WETLAND	WETLAND	LOCATION			AREA					
NUMBER	CLASSIFICATION	EUCATION		PERMANENT	IMPACTS			1		
			N.H.W.B. (NON-WETLAND)	N.H.W.B. & A.C.O.E. BANK (WETLAND)		BANK CHANNEL		TOWN	COMMENTS	
			SF	SF	LF	LF	SF			
								L		
41	PFO1E	BP		9183				D		
S2	BANK	BQ	. 161		51.			. D		
52	R3UB3	BR		714		51		D		
S2	BANK	BS	169		53			D		
46	PFO1E	вт		254				D		
49	PFO1E	BU	.n. viimudamanamanama ide me du id	2474				D		
64	PEM1E_	BV		17 _ 1				D		
63	PSS1E	BW		42				D		
63	PSS1E	BX		111				i D		
60	PFO1E	BY		17				D		
61	PFO1E	8Z	i	511				D		
VP11	VP	CA		471				D		
S3	R4SB5	СВ	i i	100		12		D	To come and and adjusted to the second secon	
S3	R4SB5	CC	The state of the s	238		26	·	D		
S4	R4SB5	CD		28		28		D		
S4	R4SB5	CE		22		7		D		
59	PFO1E	CF		98				D		
56	PEM1E	CG		195				D		
59	PFO1E	СН		4489				D		
62	PSS/PEM1E	CI		2813				D	Prime wetland	
59	PFO1E	CJ		9				D		
S5	R3UB3	СК		1548	****	73		D		
59	PFO1E	CL		14			·····	D		
59	PFO1E	CM		418				D		
62	PSS/PEM1E	CN		57	· · · · · ·				Prime wetland	

WETLAND IMPACTS	
PERMANENT IMPACTS (WETLAND)	216,083.00 SF
PERMANENT IMPACTS (NON-WETLAND)	879.00 SF
TEMPORARY IMPACTS	0.00 SF
TOTAL WETLAND IMPACTS:	216,962.00 SF
STREAM IMPACTS	
PERMANENT IMPACTS TO BANKS	351.00 LF
PERMANENT IMPACTS TO CHANNEL	2,281.00 LF
TOTAL STREAM IMPACTS:	2,632.00 LF

WETLAND CLASSIFICATION CODES							
BANK	BANK						
PEM1E	PALUSTRINE, EMERGENT, PERSISTENT, SEASONALLY FLOODED /SATURATED						
PEM1F	PALUSTRINE, EMERGENT, PERSISTENT, SEMIPERMANENTLY FLOODED						
PFO1/2E	ALUSTRINE, FORESTED, DOMINANTLY BROAD-LEAVED DECIDUOUS, MIXED WITH NEEDLE-LEAVED DECIDUOUS, SEASONALLY FLOODED /SATURATE						
PFO1E	PALUSTRINE, FORESTED, BROAD-LEAVED DECIDUOUS, SEASONALLY FLOODED /SATURATED						
PSS/PEM1E	PALUSTRINE, DOMINANTLY SCRUB-SHRUB, MIXED WITH EMERGENT, PERSISTENT, SEASONALLY FLOODED /SATURATED						
PSS1E	PALUSTRINE, SCRUB-SHRUB, BROAD-LEAVED DECIDUOUS, SEASONALLY FLOODED /SATURATED						
R3UB3	RIVERINE, UPPER PERENNIAL, UNCONSOLIDATED BOTTOM, MUD						
R4SB5	RIVERINE, INTERMITTENT, STREAMBED, MUD						
VP	VERNAL POOL						





	S	TATE	OF	NEW	1	HAMPS	НΙ	RE		
DEPARTMENT	OF	TRANSF	ORTA	TION		BUREAU	ΩF	HIGHWAY	DESIGN	

DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
13065TABLE	13065	4	25

